STOREGGA-Hydrogen

Developing Regional Hydrogen Hubs

26 November 2024



Important Notice

This presentation, together including any printed or electronic copies, any information provided or communicated during any presentation or delivery of this presentation, any oral briefing that accompanies it, and any question-and-answer session that follows such briefing (the presentation), are provided by Storegga Limited (Storegga) on the understanding that, whilst every care has been taken to ensure accuracy, no representation, warranty or undertaking (express or implied) is made and no responsibility is taken by Storegga or any employee, consultant, officer or other representative acting on it or an affiliate of its behalf (the Storegga Group) regarding its content. The Storegga Group excludes all representations, warranties, obligations and liabilities in relation to the presentation to the maximum extent permitted by law. In particular, nothing in presentation constitutes a valuation or financial, tax or legal advice, nor does it constitute an invitation to invest or otherwise provide financial support.

© Storegga 2024. The written contents of this publication are protected by copyright. All rights reserved. No part of this publication may be reproduced, stored or transmitted in any form or by any means without the permission of the copyright holder.

Hydrogen's Energy Transition Role

STOREG⁵A



Minimise demand through efficiency. Electrify where possible. Fuel switch remainder.

Ref: Scotch whisky pathway to net zero – Report for Scotch Whisky Association, Ricardo, Issue 3, May 2020

Hydrogen Project Requirements: Customer & Developer STOREG9A



Fuel switching of "Heavy Heat" and "Heavy Transport"

Hydrogen Production Plant Tanker Customer Tanker Discharge Option A Site Bay 1 Fiscal H₂ Tanker Hydrogen Tankers Export Trucks Loading Cabinet Metering Tanker Discharge Bay 2 Transporter Energy Plant(s) **Direct Private Pipeline** Hydrogen Cabinet Transport Unit(s) 20% Blend - 100% Hydrogen via Gas Distribution Network **DNO Gas** - <u>-</u> - - - - - - • • • Cabinet

STOREGDA

Distribution options:

- Compressed hydrogen tube trailers (circa 300-500bar)
- Private Pipeline
- Use of Gas Distribution Network, subject to GS(M)R change

DESNZ requirement for no risk taking intermediary

Cromarty Hydrogen

Phase 1 Developer : ScottishPower (51%) & Storegga (49%)

Phase 1 15MW electrolyser capacity (10.6MW of Hydrogen) operational within 2027.

Location: Beinn Tharsuinn Windfarm, Alness due to existing Grid Connection - 29 MW's of Renewable Generation Capacity

Offtake Strategy: Portfolio focused on Net Zero for Distilling Sector

Hydrogen Distribution: Road haul via compressed hydrogen trailers

Storegga developing Phase 2 via Site 2 and Site 3 for which HAR2 applications were submitted in April 2024 50MW at Site 2 with pipeline to anchor offtaker;

35MW at Site 3 with pipeline to anchor offtaker.

2021 Feasibility Study outlined multi-site, multi-Phase build out to 300MW.

- Expansion options at Site 2 and Site 3;
- Assessing power connections for Site 4.







Cromarty Phase 1 Project Status - Summary

STOREG⁵A

• Land Agreements

- 1 Land owner Exclusivity Agreement in place. Option / Lease progressed
- Planning
 - Application submitted October 23 & Validated January 24
 - Determination expected early 2025
- Hydrogen Production Plant
 - FEED based on 3x5MW containerised PEM electrolyser
 - ISBL split between FEED / EPC and OEM utilising Iberdrola's experience and leverage to optimise cost
- Customers Transport & Distribution Strategy
 - HSA being finalized
 - Customer site solutions design scopes being developed
 - Logistics Request for Information held



https://www.cromartyhydrogenproject.co.uk/

- Energy Supply
 - 29MW of behind the meter power available
 - Additional grid connection availability using the ScottishPower portfolio (8TWh's)
- Water Supply
 - Boreholes drilling completed and SEPA tests currently ongoing



Cromarty Phase 1 Project Timeline Schedule

STOREG^DA



Speyside Hydrogen

Land & Technical Solution

- **DESNZ HAR2** Shortlisting outcome expected 'Autumn' '24.
- Land positive engagement and necessary agreements progressing
- **70 MWe** electrolyser capacity. Buildout to 200MW via Phase 2 and 3 at Site 2
- Electrolyser OEM Selection completed Q1 '24 with design based upon specific product (PEM). OEM providing FEED support and engaged. Supply contract negotiation started.

- Production Facility FEED Contractor selected (Tier 1 EPC) and early work started.
- **Operating Philosophy** O&M and Transport Delivery philosophy development and market engagement underway.
- Planning & EIA Mott MacDonald completing EIA, survey work nearing completion. 1st Pre-Application Consultation event completed; 2nd event late November for Planning Application Q1 '25.





STOREG9A

Speyside Hydrogen

- Power Water Routes to Demand
 - **Power** will be supplied from the grid at substation located ~3km from site; connection agreement signed for 90 MVA and SHEPD progressing.
 - Power Purchase Agreement PPA Heads of Terms being finalised. Private wire discussions ongoing
 - Water 500m³/day site requirement, groundwater borehole supply
 - Water-efficient design choices air cooling; considering multi-source approach including rainwater harvesting and storage for resilience and climate change adaptation.
 - **Hydrogen transport** all export initially via tube trailers. Hydrasun completing trailer and loading configuration review. Time and Motion Study planned with haulier/consultant.
 - **Pipeline option** close proximity to gas pipeline enabling distribution via new or existing pipelines (latter subject to change to Gas Safety Management Regulations (GSMR))



STOREG_DA



https://storegga.earth/en-gb/speyside-hydrogen

Speyside Hydrogen – Next Steps in 2025

STOREG⁵A



- Agree Power Purchase
 Agreement
- Conclude customer Hydrogen Supply Agreements
- Complete Detailed Design of offtaker works
- Borehole design and construction
- Sustainable water options
- CAR licencing



- Finalise Land agreement
- Submit planning application
- Complete FEED
- Finalise OEM supply contract
- Tender and agree EPC contract
- PPC Site baseline survey

 Conclude export options including tube trailer design and pipeline options

THANK YOU

https://www.cromartyhydrogenproject.co.uk/

https://storegga.earth/en-gb/speyside-hydrogen

26 November 2024

